



U.S. ARMY CORPS OF ENGINEERS

BUILDING STRONG®

Milton Island Flood Side Intermediate Marsh



Project Location

This proposed project is located on the north shore of Lake Pontchartrain, west of the Causeway Bridge in St. Tammany Parish, Louisiana.

Project Features

This alternative consists of 272 acres of intermediate marsh restoration that would be achieved by placing dredged material in open water adjacent to the bottomland hardwood site to an elevation conducive for wetland development, followed by plating of wetland vegetation. Temporary containment features would be constructed to keep material in place. A shoreline restoration feature is proposed to repair a breach in the lake rim.

Borrow Plan

The borrow plan is to obtain material from Lake Pontchartrain, requiring a buffer of 2,000 ft between the existing shoreline and the borrow area limit.

For more information, please visit www.nolaenvironmental.gov.

U.S. ARMY CORPS OF ENGINEERS – NEW ORLEANS DISTRICT

7400 LEAKE AVE., NEW ORLEANS, LA 70118

WWW.MVN.USACE.ARMY.MIL

www.facebook.com/usacenola

www.twitter.com/teamneworleans

www.flickr.com/teamneworleans